

Name of the Work: Providing & laying of HDPE Pipe Line from NCBS STP to instem STP

Schedule of Quantities

Sl. No	Description of Items	Units	Qty	Rate	Amount
				In figures & words	
1	Providing, laying, jointing, fixing, testing, commissioning HDPE Pipes & Fittings conforming to IS:14333 with GI specials, cutting the pipes to the required lengths, threading, jointing the pipes using suitable Adhesive for HDPE (PE-100, PN-6, 110mm Dia 6 wall thickness) Pipes, chasing the walls and floors, making the holes, clamping to walls using the wooden spacers or clamps and restoring the same to the original conditions with CM 1:3, necessary excavation, testing, refilling etc. Complete all as specified and directed and as per manufacturer's specification.	Mtr	460.00		
Total Amount Rs.					
Note: The Contractor shall quote his rates in this schedule of quantity. Submission of tender in any other format is liable for rejection.					

Total Amount in words

Signature of the Contractor

Date

Address Seal