

**Name of the work - Providing and fixing of homogeneous vinyl floor in Mass Spectrometer
Facility at basement of Admin block**

Schedule of Quantities

Sl. No	Description	Units	Qty	Rate	Amount
				in figures & words	
1	Providing and fixing of Gerflor or equivalent range of approved colour and shade of homogeneous vinyl floors of size 200 cmx20m x 2.00 mm with:Static electrical propensity < 2.0, wear resistance < 2.0 mm ³ , Residual indentation of ~0.02mm, colour fastness of stage < 6 mm,thermal conductivity 0.25W/(m.K) and Anti-bacterial activity < 99% inhibits growth.. Gerflor Lab grede vinyl floor should be installed on a smooth , hard and absolutely leveled sub floor. . Clean the floor with a liquid detergent diluted with warm water stubborn marks can be removed with a fine abrasive powder and scouring pad. Rinse properly with clean water to remove all traces of detergent. Polishing or surfaces coatings on Lab grade floors must not be used as these will leave a film over the floor surface which will alter the conductivity of the installation., including skirting.	Sqm	30.00		
Total amount Rs.					
<u>Note:</u> The Contractor shall quote his rates in this schedule of quantity. Submission of tender in any other format is liable for rejection					

Total amount in words:

Signature of the contractor

Date:

Address:

Seal: