

**NATIONAL CENTRE FOR BIOLOGICAL SCIENCES
TATA INSTITUTE OF FUNDAMENTAL RESEARCH**

**Name of the work :-Providing and fixing Insulation for Hot Water Line on terraces
of Housing Blocks at CB Site**

Schedule of Quantities

Sl. No.	Description of the item	Unit	Qty	Rate	Amount
				(in Figures & words)	
1	Providing and fixing thermal insulation with Resin bonded rock wool conforming to IS: 8183, density 48kg/m ³ , 50 mm thick, with Chicken mesh wrapped in 200 G virgin Polythene bags placed over existing position by criss- crossing GI wire and Covered with Aluminum Cladding 26 Gauge.	Rmt	1650.00		
Total Rs.					
Note: The Contractor shall quote his rates in this schedule of quantity. Submission of tender in any other format is liable for rejection.					

Total Amount in words:

Signature of the Contractor:

Date:

Address: