NATIONAL CENTRE FOR BIOLOGICAL SCIENCES TATA INSTITUTE OF FUNDAMENTAL RESEARCH

Name of the work: Providing and fixing GI and CPVC Pipe line for Solar Panels at NCBS

Schedule of Quantities

S1. No.	Description the the items	Unit	Qty	Rate (in figures & words)	Amount
1	Providing, laying, jointing, fixing, testing, painting,	Rmt	260.00		
	commissioning GI pipes, medium grade conforming to				
	IS:1239 with a minimum weight as follows including GI				
	specials, cutting the pipes to the required lengths, threading,				
	jointing the pipes, chasing the walls and floors, making the				
	holes, clamping to walls using wooden spacers or clamps				
	and restoring the same to the original conditions with CM				
	1:3, necessary excavation, testing, refilling etc. Complete all				
	specified and directed. (Ref. Fig. No.CED: PH2.1 of PH				
	Engineering Specification)				
	For external works - 25mm NB (2.46 kg/m)				
				· · ·	
2	Providing and fixing Chlorinated Polyvynyl Chloride (CPVC)				
	pipes (SDR 13.5) conforming to IS:15778, having thermal				
	stability for hot and cold water supply including all CPVC				
	plain & brass threaded fittings including fixing the pipe with				
	clamps at 1.00m spacing. This includes jointing of pipes and				
	fittings with one step CPVC solvent cement and testing of				
	joints complete as per direction of Engineer-in-Charge etc.,				
	for INTERNAL WORKS EXPOSED ON WALLS with:				
	CPVC pipes, 25mm outer dia	Rmt	260.00		
				Total Rs.	
loto: 7	The Contractor shall quote his rates in this schedule of quatity.	01		1	<u> </u>

Total Amount in words:

Signature of the Contractor:

Date:

Address: