Name of the work - Maintenance for 3rd floor atrium glass roofs at SLC building

Schedule of Quantities

S1. No	Description	Units	Qty	Rate	Amount
				in figures & words	
1	Careful removal of existing silicon sealant filled in	Rmt	480.00		
	the joints of double glass panels placed at atrium				
	roof and refilling with dow corning or equivalent				
	weather proofing sealant with beaker rods of				
	suitable size, masking the glass surface before				
	application, necessary application tools and clearing				
	excess materials etc and as per the direction of EIC.				
			Tota	l amount Rs.	
Note: T	The Contractor shall quote his rates in this schedule of format is liable for rej	-	ty. Subr	nission of tend	er in any othe

Total amount in word	ls:		
Signature of the cont	ractor		
Date:			
Address:			
Seal:			