

Name of work : Conversion of existing Bath rooms to EWC rooms In Admin Building

Blank Schedule of Quantities

Sl. No.	Description of the item	Unit	Qty	Rate	Amount
1	Dismantling stone slab flooring and dadoing laid in cement mortar including stacking of serviceable material and disposal of unserviceable materials within 50m lead.	sqm	4.70		
2	Providing and laying 16 to 18mm thick of approved colour mirror polished granite stone slabs flooring of approved colour and shade using mirror polished granite stone slabs of approved size sizes as per the site conditions, water cut quality, machine cut to required size, laid over a bed of 20mm thick cement mortar 1:6 and cement slurry at the rate of 4.4kg/sqm for bedding and jointing including grouting the joints with pigments to match the shade of the slabs, finishing to required level, curing, cleaning, mopping, etc; complete all as per specifications at all heights in all floors. Flooring cut to required size from bigger gang size slabs of approved colour	sqm	2.55		
3	Providing and laying Stone tile work for wall lining up to 10m height with special adhesive like araldite / equivalent over 12mm thick bed of cement mortar 1:3 (cement : coarse river sand) including pointing in white cement with an admixture of pigment to match the stone shade with tile (mirror polished and machine cut edges) using 8mm thick, Granite black stone	sqm	2.20		

Sl. No.	Description of the item	Unit	Qty	Rate	Amount
4	<p>Providing and Fixing European Water Closet Suite P trap (with Metropole flush valves Regular models) comprising of:</p> <p>A) Best Indian make white glazed vitreous Chinaware European water closet, with wash down pattern of approved make with trap as mentioned below conforming IS 2556 Part-II bearing ISI mark fixed to wall with necessary teak wood plugs, CP brass screws / bolts No. 8x37 etc., of LARA model catalogue No. 20069 or Equivalent.</p> <p>B) Providing and fixing of metropole flush valves regular model No. FLV10855A or equivalent with cover plate embeded in wall and making necessary water supply connections from existing water supply line including making good in CM 1:5 after cutting the masonry wall.</p> <p>C) White color Plastic seat and cover of approved make with CP pillar hinges conforming to IS:2548</p>	Each	2.00		
5	<p>Supplying & fixing of factory made composite door shutter with frame and single shutter manufactured by M/s. Fimen Fibre Products Pvt. Ltd., or equivalent. The door shutter shall be of rigid GRP sandwich composite structure of 30mm thick (minimum) laminated on all sides with GRP skin fabricated using U.V. stabilized Isophthalic gel coat and one layer of 450 GSM E glass chopped strand mat (CSM) impregnated with polyester resin. The thickness of skins shall not be less than 1.5mm. Expanded polystyrene structural foam panel of density 20kg/cum shall be used as core material for the whole areas of door except the wooden frame structure.</p>	Sqm	6.45		

Sl. No.	Description of the item	Unit	Qty	Rate	Amount
	The wooden reinforcements made of seasoned salwood block of minimum cross section of 70 x 26 for lock side 40 x 26 all round forming the framework for shutter and minimum of 75mm wide intermediate strip for the width of the door for fixing locks and fixture and shall conform to IS-4020-1998. The finish of the shutter be without grains and of approved colour etc., complete all as per manufacturers specifications at all heights.				
Total Amount Rs.					
Note: The Contractor shall quote his rates in this schedule of quantity. Submission of Quotation in any other format is liable for rejection.					

Total Amount in words:

Signature of the Contractor:

Date:

Address: