Name of Work : Proposed Space for Lab support office at 1st Floor of Eastern laboratories

Schedule of Quantity

SINo	Items of Description	Unit	Qty	Rate	Amount
1	Providing and fixing aluminium work for doors, windows,		-		
•	ventilators and partitions with extruded built up standard				
	tubular sections/ appropriate Z sections and other sections of				
	approved make conforming to IS: 733 and IS: 1285, fixing			-	
	The state of the s				
	with dash fasteners of required dia and size, including				
	necessary filling up the gaps at junctions, i.e. at top, bottom				
	and sides with required EPDM rubber/ neoprene gasket etc.				
	Aluminium sections shall be smooth, rust free, straight,				
	mitred and jointed mechanically wherever required including				
	cleat angle, Aluminium snap beading for glazing / paneling,				
	C.P. brass / stainless steel screws, all complete as per				
	architectural drawings and the directions of Engineer-in-				
	charge. (Glazing, paneling and dash fasteners to be paid for				
	separately):				
1a	Powder coated aluminium (minimum thickness of powder	Kg	55.00		
	coating 50 micron)				
	Rate in Words:				
1b	For shutters of doors, windows & ventilators including		15.00		
	providing and fixing hinges/ pivots and making provision for				
	fixing of fittings wherever required including the cost of				
	EPDM rubber / neoprene gasket required (Fittings shall be				
	paid for separately)				
	Powder coated aluminium (minimum thickness of powder	Kg	15.00		
	coating 50 micron)				
	Rate in Words:				
2	Providing and fixing glazing in aluminium door, window,				
	ventilator shutters and partitions etc. with EPDM rubber /			#	
	neoprene gasket etc. complete as per the architectural				
	drawings and the directions of engineer-in-charge . (Cost of				
	aluminium snap beading shall be paid in basic item):				
	With float glass panes of 5 mm thickness (weight not less	Sqm	7.00		
	than 12.50 kg/sqm)				
2			(00		
3	Providing and fixing 9mm thick flat pressed three layered	Sqm	6.00		
	wood based melamine faced prelaminated particle board				
	bonded with Phenol formaldehyde with a decorate laminate				
	of same colour on both sides - NOVOPAN PLT / BHUTAN				
	BOARD - Interior grade or equivalent, including cutting to				
	required size and shape, fixing with aluminium glazing clips				
	or triangular beading (measured and paid under item 1				
	above) including screws, putty etc., complete. Rate in Words:				
4	Providing and fixing Brass 100mm mortice latch and lock	Nos	2.00		
4	with 6levers without pair of handles (best make of approved	1105	2.00		
	quality) for aluminium doors including necessary cutting and				
	making good etc.complete.				
	Rate in Words:				

SI No	Items of Description	Unit	Qty	Rate	Amount
5	Providing and Fixing in position Dorma TS-68 door closer or	Nos	2.00		
	Equivalent make.Complete all as per directions of Engineer-in-Charge.				
	Rate in Words:				
6	Providing and fixing false ceiling at all height including				
	providing and fixing of frame work made of special sections,				
	power pressed from M.S. sheets and galvanized with zinc			181	
	coating of 120 gms/sqm (both side inclusive) as per IS: 277				
	and consisting of angle cleats of size 25 mm wide x 1.6 mm				
	thick with flanges of 27 mm and 37mm, at 1200 mm centre to				
	centre, one flange fixed to the ceiling with dash fastener 12.5				
	mm dia x 50mm long with 6mm dia bolts, other flange of				
	cleat fixed to the angle hangers				
	of 25x10x0.50 mm of required length with nuts & bolts of				
	required size and other end of angle hanger fixed with				
	intermediate G.I. channels 45x15x0.9 mm running at the				
	spacing of 1200 mm centre to centre, to which the ceiling				
	section 0.5 mm thick bottom wedge of 80 mm with tapered				
	flanges of 26 mm each having lips of 10.5 mm, at 450 mm				
	centre to centre, shall be fixed in a direction perpendicular to				
	G.I. intermediate channel with connecting clips made out of				
	2.64 mm dia x 230 mm long G.I. wire at every junction,				
	including fixing perimeter channels 0.5 mm thick 27 mm high				
	having flanges of 20 mm and 30 mm long, the perimeter of				
	ceiling fixed to wall/partition with the help of rawl plugs at				
	450 mm centre, with 25mm long dry wall screws @ 230 mm				
	interval, including fixing of gypsum board to ceiling section				
	and perimeter channel with the help of dry wall				
	screws of size 3.5 x 25 mm at 230 mm c/c, including jointing	9.5			
	and finishing to a flush finish of tapered and square				
	edges of the board with recommended jointing compound,				
	jointing tapes, finishing with jointing compound in 3 layers				
	covering upto 150 mm on both sides of joint and two				
	coats of primer suitable for board, all as per manufacturer's				
	specification and also including the cost of making openings				
	for light fittings, grills, diffusers, cutouts made with				
	frame of perimeter channels suitably fixed, all complete as				
	per drawings, specification and direction of the Engineer in				
	Charge but excluding the cost of painting with :12.45.1 12				
	mm thick tapered edge plain board conforming to IS: 2095-				
	(Part I): 2011 (Board with BIS Certification marks)				
	12 mm thick calcium silicate false ceiling/Partitions	Sqm	3.00		
	Rate in Words:	•			
	NOTE: For lighting fittings, grills diffuses and cut-outs etc.,				
	have to be made with the frame of perimeter channels of size				
	20mm x 27mm x 30mm x 0.55mm thick supported suitable				
	and should be considered as per drawing.				
			10		

,

SI No	Items of Description	Unit	Qty	Rate	Amount		
7	Wall painting with premium acrylic emulsion paint of interior						
	grade, having VOC (Volatile Organic Compound) content						
	less than 50 grams/ litre of approved brand and manufacture,						
	including applying additional coats wherever required to						
	achieve even shade and colour.						
	Two coats	Sqm	90.00				
	Rate in Words:						
	Total Amount Rs.						

Note: The contractor shall quote his rates in this schedule of quantity. Submission of tender in any other format is liable for rejection.

for rejection.		
Total amount in words:		
Signature of the contractor:		
Date:		
Address:		