

Name of work: " Internal painting for allotted flats of Sugandi, Kepala, Jaji and Gulabi in Housing at CB Site"

NIT No:NCBS/Maint(civil)/613/NIT-153/2022 Dated: 18/07/2022.

Schedule of Quantity

SI no:	Description of Items	Unit	Qty	Rate	Amount
1	Wall painting with premium acrylic emulsion paint of interior grade with One or more coats, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand & colour and manufacture, including applying additional coats / necessary touch up putty wherever required to achieve even shade and colour: as per specifications and as directed by EIC.	Sqm	10000		
Rate in words:					
2	Painting with synthetic enamel paint with One or more coats of approved brand and manufacture of required colour to give an even shade as per specifications and as directed by EIC.	Sqm	1100		
Rate in words:					
3	French spirit polishing with One or more coats of approved brand and manufacture of required colour to give an even shade as per specifications and as directed by EIC.	Sqm	500		
Rate in words:					
4	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts& bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre,	Sqm	50		

SI no	Description of Items	Unit	Qty	Rate	Amount
	to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval. including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and				
	square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks)				
	Rate in words:				
5	Providing and applying plaster of paris putty of 2 mm thickness over surface to prepare the surface even and smooth complete all as per specifications and as directed by EIC.	Sqm	50		
	Rate in words:				

Sl no	Description of Items	Unit	Qty	Rate	Amount
6	Wall painting with premium acrylic emulsion paint of interior grade with two or more coats, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand & colour and manufacture, including applying additional coats / necessary touch up putty wherever required to achieve even shade and colour. as per specifications and as directed by EIC.	Sqm	50		
Rate in words:					
				Total Amount	
<p>Note : The contractor shall quote his rates in this schedule of quantity. Submission of tender in any other format is liable for rejection.</p>					

Total Amount in words:

Signature of contractor.

